ENGINEERING DEPARTMENT.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Abstract Notice, dated 22nd—26th April 1937.

The attention of the public is invited to the Notification dated 21st April 1937, calling for tenders for "Constructing masonry reservoir and suction well, etc.," for water supply to Saklespur Town," published in page 628-629, Part VI of the *Mysore Gazatte*, dated 29th April 1937.

The last date of receiving tenders is fixed on 17th May 1937.

B. R. GARUDACHAR,
Sanitary Engineer.

BANGALORE DIVISION.

Notification dated 26th April 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 24th May 1937, for restoring Madagondanahalli Shettikere, Register No. 260 of Dodballapur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1938.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. to 5 P.M.

3. Tender should be submitted on printed forms which may be obtained form the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees Two hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Madagondanahalli Shettikere, Register No. 260 of Dodballapur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond after depositing an additional sum of Rs. 250 in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Execuitve Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Approximate quantities required for restoring and improving Madagondanahalli Shettikere Register No. 260 (Minor Tank), Dodballapur Taluk.

No.	Items of work	Unit	Quantity	Rate sanctioned	Rate quoted in	
					Figures	Words
	Bund.			Rs. a. p.		
1	Jungle clearing with roots ..	Grade	14	1 4 0		
2	Removing ant-hills and refilling with sand	No.	6	0 12 0		
3	Cutting grips and trenches to old bund	Grade	18	2 4 0		
4	Earthwork raising bund with watering and consolidation including lead and lift	C.yd.	9,420	0 3 6		

No.	Items of work	Unit	Quantity	Rate sanctioned	Rate quoted in Figures	Rate quoted in Words
				Rs. a. p.		
5	Rough stone pitching 9" thick ..	S.yd.	1,183	0 4 0		
6	Turfing the slopes of bund and watering till it grows ..	,,	6,143	0 0 10		
7	Providing and fixing new grade stones with painting, etc., with bed stones complete	Each	18	2 0 0		
8	Do Index stones do	,,	18	0 5 0		
9	Do Register No. stone do	,,	1	2 8 0		
10	Do B. M. stone do	,,	2	2 8 0		
11	Do Guage stone do	,,	1	14 0 0		
	Masonry sluice (Right).					
1	Earthwork cut opening the bund and refilling the same after construction	C.yd.	105	0 6 0		
2	Earthwork excavating foundation ..	,,	14	0 3 0		
3	Burnt stone jelly in surki concrete foundation	C.ft.	100	0 4 0		
4	Burnt brick in surki mortar ..	,,	485	0 5 0		
5	Burnt stone slabs 6" dressed and fixed in surki mortar	S.ft.	150	0 6 0		
6	Surki mortar plastering ..	Sqr.	5·22	4 0 0		
7	Cutting holes in orifice slab and guide slabs ..	Each	4	1 0 0		
8	Providing plug with iron rod and locking arrangement, etc., complete ..	,,	1	15 0 0		
	Waste Weir.					
1	Earthwork excavation for foundation	C.yd.	26	0 3 6		
2	Burnt brick in surki mortar ..	C.ft.	565	0 4 6		
3	Removing and refixing old burnt stone slabs in surki mortar ..	S.ft.	272	0 2 0		
4	Removing and resetting old stone apron with required new jelly ..	C.yd.	70	0 14 0		
5	Surki plastering ..	Sqr.	3·00	3 0 0		
6	Earthwork excavation for draft and approach clearing and using the same to training banks *including* consolidation ..	C.yd.	132	0 3 0		
	Silt Trap.					
1	Earthwork excavating for foundation	C.yd.	25	0 3 6		
2	Burnt stone jelly surki concrete ..	C.ft.	140	0 4 0		
3	Burnt size stone in surki mortar ..	,,	400	0 5 0		
4	Burnt stone slabs 6" thick dressed and fixed in surki mortar ..	S.ft.	100	0 6 0		
5	Cement pointing ..	Sqr.	3·00	3 0 0		
6	Rough stone apron new with jelly wedging	C.yd.	6	1 12 0		

M. K. NARASIMHA IYER,
Executive Engineer.

SHIMOGA DIVISION.

Notification dated 30th April 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, upto 2 P.M. on Saturday the 29th May 1937, for "the extension of Maternity Hospital Building at Shimoga". An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of November 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a treasury chellan for having deposited a sum of Rs. 480 as earnest money and be superscribed "Tender for Maternity Hospital Building extension at Shimoga," in defaut of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Shimoga Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No Enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rates will not be accepted.

13. Work should be according to departmental specifications.

14. Transfer of works to other parties or subletting of contractors is prohibited.

15. Monthly progress should not be less than Rs. 1,200 and the work should be completed by the end of November 1937.

16. Mysore timber alone should be purchased by the contractor from the Mysore Government Forest timber yards.

Abstract estimate for extension of Maternity Hospital Building at Shimoga.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavation and filling in basement including watering and tamping, etc. ..	C.yd.	0 5 0	176	
2	Stone jelly concrete in surki mortar	C.ft.	0 5 0	2,174	
3	Size stone in chunam including bond stones at every 6' along walls	,,	0 6 6	2,888	
4	Burnt stone plinth slab 6" thick 2 lines dressed and fixed in lime mortar including cement pointing	S.ft.	1 0 0	220	
5	Cement pointing to basement (1 : 3)	Sqr.	4 0 0	5·43	
6	Drilling holes of 4"×5"×3" in burnt stone slabs for fixing door frames	Each	0 8 0	10	
7	Burnt brick in lime mortar	C.ft.	0 4 6	2,769	
8	Burnt stone slabs 6" thick roughly dressed and fixed in mortar	S.ft.	0 10 6	298	

No	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
9	Circular pillar 16″ at bottom and 13½″ at top with ordinary quadrant bricks in cement mortar 1:3 and bond slabs at every 3′ height with capitals and bases including nice plastering as per design	Each	20 0 0	6	
10	Teakwood doors with 4′×6″ frames 1½″ thick panelled shutters, ⅓ at bottom and ⅔ pinheaded Marocco glazed shutters at top with 3 pairs of brass parliamentary hinges and 30″ brass tower bolts at top, 12″ at bottom and 9″ ones at centre with 2 pairs of brass door handles including C. I. fan light at top, etc., complete with 2 coats of Varnishing (only Mysore teak purchased from Government Forest Depot to be used)	S.ft.	2 4 0	80	
11	Do inside doors without fan lights.	,,	2 0 0	96	
12	Teakwood doors with 3½″×5″ frames and 1½″ thick battened shutters with cut hinges, etc., complete including 2 coats of gray graphite silicate painting	S.ft.	2 0 0	54	
13	Teakwood windows with 3½″×5″ frames and 1¼″ thick panelled shutters at bottom and glazed shutters at top with pinheaded Moracco glazed (in 4 halves) with C. I. ventilators at top for 1½′ with brass fittings, etc., (parliamentary hinges for windows opening into verandah) two coats of varnishing or grey graphite painting for inside and outside windows respectively	S.ft.	2 8 0	147	
14	Providing and fixing R.C.C. ventilators ..	S.ft.	1 6 0	18	
15	Providing and fixing T.W. sun shades including 2 coats of grey graphite painting (for windows out side)	Each	8 0 0	5	
16	R.S. beams including hoisting and fixing, etc., complete 18″×6″ at 55 lbs. per R.ft. ..	Cwt.	12 0 0	33·9	
17	Boxing girder in brick in cement mortar (1:3) with exmet reinforcement and chunam plastering, etc., complete..	R.ft.	0 12 0	60	
18	Terracing with one course of ordinary bricks laid edge wise in cement mortar (1: 2½) with reinforcements langl. and cross wise, at each joint and over which 2½″ cement concrete and 3″ to 6″ thick brick kappi in quick lime, 2 courses of colas ¼″ thick to be laid with dangry cloth and 2 courses of flat tiles laid in lime mortar over it and bolts top and bottom surface finished with nice plastering and white washed	Sqr.	80 0 0	16·98	
19	Parapet wall with brick in mortar 2′ high and 9″ thick including nice plastering, etc., complete as per existing design	R.ft.	1 0 0	223	
20	9″ thick plain cornice including nice plastering, etc., complete	,,	0 4 0	218	
21	Chunam plastering ½″ thick	Sqr.	3 4 0	38·62	
22	White washing 2 coats	,,	0 4 0	38·62	
23	Colour washing 2 coats	,,	0 5 0	5·43	
24	4½″ thick partition walls in cement mortar (1:3) with exmet reinforcement for every alternative course including cement plastering to both faces with ⅛″ snowcrete white cement rendering	S.ft.	0 11 6	200	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
25	Cement mortar plastering ½" thick with white cement rendering ⅛" thick	Sqr.	13 0 0	2·52	
26	Flooring with 4" stone jelly concrete in lime mortar and 1½" cement concrete (1 : 3 : 6) with ½" thick red coloured cement (1 : 3) plastered and cut into 6' squares with expansion joints at every 6' apart	Sqr.	27 0 0	13·25	
27	Red coloured cement skirting for walls ..	Sqr.	16 0 0	1·86	
28	Milk white glazed tiled flooring (tiles of best Japan make) on 4" jelly concrete in lime mortar and set in cement mortar 1 : 3 and pointed with white cement	Sqr.	75 0 0	1·14	
29	4" diameter C.I. rain water down pipes fixed in cement	R.ft.	1 6 0	120	
30	C.I. ornamental spants including fixing ..	Each	10 0 0	3	
31	Teakwood wrought and putup including 2 coats of grey graphite painting (only Mysore Teak to be used)	C.ft.	4 4 0	40	
32	Sanitary fittings and water supply	L. S.	..	..	
33	Electrical fittings	L. S.	..	..	

P. SUBBA RAO,
Executive Engineer.

KADUR DIVISION.

Notification dated 29th April 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 17th May 1937, for constructing (1½ Blocks) Cooly Quarters at Tarikere. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 245 (Two hundred and forty-five only) in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for constructing Cooly Quarters at Tarikere," in default of which tenders will be rejected. Applications or representations to adjust earnest money out of pending bills will not be considered.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for constructing Cooly Quarters at Tarikere.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavation	C.yd.	0 4 6	35	10
2	Stone jelly in lime mortar concrete	C.ft.	0 5 0	287	90
3	Size stone in clay	,,	0 4 0	943	236
4	Burnt brick in clay	,,	0 4 0	2,180	545
5	Burnt stone slabs 4" thick roughly dressed	S.ft.	0 8 0	155	78
6	Chunam plastering	Sqr.	4 6 0	45·19	198
7	Pointing with cement mortar	,,	5 0 0	1·37	7
8	White and colour washing, 2 coats	,,	0 4 6	46·56	13
9	Doors with teakwood frame and battened shutters 1" thick with iron fittings, hinges, etc., complete	S.ft.	1 12 0	78	136
10	Windows with teakwood frame and battened shutters 1" thick with iron bars $\frac{5}{8}$" thick hinges, etc., complete	,,	2 0 0	30	60
11	Shelves with T.W. frame with shutters planks 1" thick	,,	1 0 0	48	48
11(a)	R.C. perforated ventilators	,,	1 4 0	18	23
12	Silver grey painting	Sqr.	3 8 0	2·16	8
13	Teakwood-wrought and put up including wood oiling	C.ft.	5 0 0	33·89	269
14	Roofing with 1st class Mangalore Tiles on teakwood reepers 2"×1" including wood oiling	Sqr.	32 0 0	13·88	444
15	Ridge tiles set in mortar and cement pointed	R.ft.	0 14 0	67	59
16	Ventilating tiles	Each	1 0 0	16	16
17	Constructing mortar bands including chunam plastering	R.ft.	0 4 0	32	8
18	Flooring with 3" chunam concrete over $1\frac{1}{2}$" cement concrete, cement plastering $\frac{1}{2}$", coloured and lined, etc., complete	Sqr.	20 0 0	6·98	140
19	Constructing sinks	Each	4 0 0	4	16
20	Providing stone mortar and pestle	,,	5 0 0	4	20
21	Constructing surki concrete drain including cement plastering 1 : 3	R.ft.	0 8 0	54	27
22	Removing debris and levelling ground giving a slope including removing earth 3" to 6" depth	S.yd.	0 1 0	1,000	63
23	Providing and fixing T.W. doors frame with battened shutters in the rear wall whereas windows is shown in the plan	S.ft.	1 12 0	78	137
24	Providing and fixing lintel slabs 4" thick roughly dressed	,,	0 8 0	50	25
25	Constructing a Dwarf wall in front verandah with burnt brick in mortar	C.ft.	0 5 0	45	14
26	Providing and fixing expanded metal with T.W. frame 2"×3" including a door	S.ft.	0 12 0	263	197
27	Chunam plastering	Sqr.	4 6 0	173	8
28	Providing and fixing teakwood eave board 9" wide and 1" thick	R.ft.	0 9 0	150	84
29	Silver greay painting to doors and expanded metal	Sqr.	3 8 0	4·19	15
30	Constructing one unit of latrine as per drawing N. G. 257	L. S.	(As per details below)		160
	Total				3,154
	Contingencies 5 per cent				158
	Grand Total				3,312
	N.B.—Quantities given are for one Block only.				

No.	Items of work	Unit	Quantity	Rate	Cost
	Abstract for Latrine Construction.		Rs. a. p.		Rs.
1	Earthwork excavation	C.yd	0 4 6	4	1
2	(*a*) Stone in mortar foundation and basement ..	C.ft.	0 4 6	130	37
	(*b*) Burnt brick in mortar: superstructure ..	,,	0 5 0	193	60
	(*c*) Chunam plastering	Sqr.	4 0 0	4·91	20
	(*d*) Cement pointing	,,	5 0 0	0·56	3
	(*e*) White and colour washing 2 coats ..	,,	0 4 6	5·47	2
	(*f*) Cement plastering ½" thick	,,	10 0 0	80	8
	(*g*) Tar washing 2 coats	,,	2 8 0	0·63	2
3	Flooring with 3" concrete and 1½" cement concrete and plaster ½" thick in cement ..	,,	20 0 0	0·38	8
4	Fixing outlets constructing drain	No.	8 0 0	1	8
5	Providing galvanized iron sheet tubs 12"×6" complete with tarring	,,	0 12 0	6	5
	Total ..				154
	Contingencies ..				6
	Grand Total ..				160

Notification dated 29th April 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 17th May 1937, for constructing (1½ Blocks) Cooly Quarters at Chikmagalur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 245 (rupees two hundred and forty-five only) in cash or Government Promissory Notes as earnest money, and be superscribed, "Tender for constructing Cooly Quarters at Chikmagalur," in default of which tenders will be rejected. Applications or representations to adjust earnest money out of any pending bills will not be considered.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for constructing Cooly Quarters at Chikmagalur.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavation	C.yd.	0 4 6	35	10
2	Stone jelly in lime mortar concrete	C.ft.	0 4 6	287	81
3	Stone in clay ..	,,	0 4 0	943	236

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
4	Burnt brick in clay	C.ft.	0 4 0	2,180	545
5	Burnt stone slabs 4″ thick roughly dressed ..	S.ft.	0 8 0	155	78
6	Chunam plastering	Sqr.	4 6 0	45·19	198
7	Pointing with cement mortar	,,	5 0 0	1·37	7
8	White and colour washing, 2 coats	,,	0 4 6	46·56	13
9	Doors with teakwood frame and battened shutters 1″ thick with iron fittings, hinges, etc., complete	S.ft.	1 12 0	78	136
10	Windows with teakwood frame and battened shutters 1″ thick with iron bars $\frac{5}{8}$″ thick hinges complete	,,	2 0 0	30	60
11	Shelves with T.W. frame with shutters planks 1″ thick	,,	1 0 0	48	48
11(*a*)	R. C. perforated ventilators	,,	1 4 0	18	23
12	Silver grey painting	Sqr.	3 8 0	2·16	8
13	Teakwood wrought and put up including wood oiling	C.ft.	5 0 0	53·89	269
14	Roofing with 1st class Mangalore Tiles on teakwood reepers 2″×1″ including wood oiling..	Sqrs.	28 0 0	13·88	389
15	Ridge tiles set in mortar and cement pointed ..	R.ft.	0 12 0	67	50
16	Ventilating tiles	Each	1 0 0	16	16
17	Constructing mortar bands including chunam plastering	,,	0 4 0	32	8
18	Flooring with 3″ chunam concrete over 1½″ cement concrete plastering ½″ coloured and lined, etc., complete	Sqr.	20 0 0	6·98	140
19	Constructing sinks	Each	4 0 0	4	16
20	Providing stone mortar and pestle	,,	5 0 0	4	20
21	Constructing surki concrete drain including cement plastering 1 : 3	R.ft.	0 8 0	54	27
22	Removing debris and levelling ground giving a slope including removing earth 3″ to 6″ depth.	S.yd.	0 1 0	1,000	63
23	Providing and fixing T.W. doors frame with battened shutters in the rear wall where as windows is shown in the plan	S.ft.	1 12 0	78	137
24	Providing and fixing linted slabs 4″ thick roughly dressed	,,	0 8 0	50	25
25	Constructing a Dwarf wall in front verandah with burnt brick in mortar	C.ft.	0 5 0	45	14
26	Providing and fixing expanded metal with T.W. frame 2″×3″ including a door	S.ft.	1 0 0	263	263
27	Chunam plastering	Sqr.	4 6 0	1·73	8
28	Providing and fixing Teakwood eave board 9″ wide, 1″ thick	R.ft.	0 8 0	150	75
29	Silver grey painting to doors and expanded metal	Sqr.	3 8 0	4·19	15
30	Constructing one unit of latrine as per drawing No. G. 257 as per details below :— ..	L. S.	..	..	160
	Total ..				3,138
	Contingencies at 5 per cent ..				157
	Grand Total ..				3,295
	N.B.—Quantities given are for one Block only.				
	Abstract for Latrine Construction.				
1	Earthwork excavation	C.yd.	0 4 6	4	1
2	(*a*) Stone in mortar foundation and basement ..	C.ft.	0 4 6	130	37
	(*b*) Burnt brick in mortar : superstructure ..	,,	0 5 0	193	60
	(*c*) Chunam plastering	Sqr	4 0 0	4·91	20
	(*d*) Cement pointing	,,	5 0 0	0·56	3
	(*e*) White and colour washing 2 coats ..	,,	0 4 6	5·47	2
	(*f*) Cement plastering ½″ thick	,,	10 0 0	0·80	8
	(*g*) Tar washing 2 coats				

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
4	Fixing outlets constructing drain	No.	8 0 0	1	8
5	Providing galvanized iron sheet tubs 12″×6″ ..	,,	0 12 0	6	5
	Total ..				154
	Contingencies ..				6
	Grand Total ..				160

L. A. H. WINCLAIR,
Executive Engineer.

MEDICAL DEPARTMENT

THE GOVERNMENT AYURVEDIC AND UNANI COLLEGE, MYSORE.

Notification, dated 27th April 1937.

Notice calling for tenders for the supply of drugs and articles of food to the in-patient and the pharmacy sections attached to the Government Unani Hospital, Mysore.

Notice is hereby given that sealed tenders will be received at the Office of the Principal, Government Ayurvedic and Unani College, Mysore, up to 15th June 1937, for the supply of drugs and articles of food for the year 1937-38, commencing from 1st of July 1937 as noted in the appended schedule. The annual quantities noted in the schedule are approximate and the successful tenderer will be required to supply more or less according to requirements.

2. No tenders will be received after the date abovementioned.

3. Tenders to be superscribed as " (a) Tender for the supply of diet articles of food and other miscellaneous articles for the Government Unani Hospital, Mysore, for the year 1937-38, (b) Tender for the supply of drugs and other articles for the Government Unani Pharmacy, Mysore, for the year 1937-38."

4. No tenders will be received unless accompanied by a deposit of Rs. 50 through a chellan from the Government Treasury.

5. The tenders will be opened by the Principal, Government Ayurvedic and Unani College, Mysore, at his office on 16th June 1937 at 11 A.M. precisely, in the presence of such tenderers, as may choose to attend.

6. The rate for each item must be specified in the list appended hereto. The value of each tender must be worked out according to the rates tendered and the total value must also be entered in ink. Tenders not conforming to this rule will be rejected.

7. The quantities stated in the list are not guaranteed.

8. The deposit of the successful tenderer will be retained and forfeited to Government if he fails to complete the contract within the time which will be specified in the intimation letter of acceptance of his tender.

9. No advance of cash will be made to the contractor; payments for the articles supplied will be made in due time after the articles are received, and on his producing necessary bill with voucher.

10. The contract must not be sublet.

11. In case the contractor ceases to abide by the contract at any time during the currency thereof, he shall forfeit the security money to Government and also be bound to make good to Government any loss which may arise from such cessation.

12. The successful tenderer should supply the required quantities in accordance with the indents received, which will be subject to alteration at any time up to the time of despatch.

13. The successful tenderer will be required to guarantee that none of the articles supplied are adulterated. Any supplies that are found unfit for use on account of any reason will be summarily rejected, and must be removed by the contractor at once.

14. Articles ordered should be of the best quality and fit to be used without any extra labour or wastage and should be delivered at the hospital, free of all charges, diet articles within 8 A.M. daily and other articles not later than 12 hours after the receipt of the indent by the contractor.

15. If the supplies are satisfactorily made during the year to which the contract relates, the continuance of the contract for a term of three years will be considered.

16. The decision of the Vice-President of the Government Ayurvedic and Unani College Committee, Mysore, will be final in all questions relating to the contract; he does not bind himself to accept the lowest or any tender or to assign any reason for not doing so.

17. All articles, except when mentioned otherwise, should be of the first sort cleaned, and any articles rejected on account of inferiority should be promptly replaced by articles of the required quality or will be purchased by the hospital authorities from outside and the charges debited to the contractor.

18. As soon as the intimation of the acceptance of his contract is sent, the contractor should execute a bond on a stamped paper of 12 annas for the satisfactory execution of his contract.

[illegible] contractor should also arrange for the ready supply of green herbs in bundle,